

The 14th June 1888.

Under para 14 of the conditions of schedule contract bond, notice is hereby given that fresh sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 25th June 1888, for restoring the Gurgadahalli Tank of Tipper Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money and be superscribed "Tender for restoring the Gurgadahalli Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 6 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for restoring Gurgadahalli Tank, Registered No. 70, Tipper Taluk.

Items of Work.		Per.	Quantity.	Rate.	Cost.	Total.
Bund—						
Earthwork	C. Yd.	19,769			
New stone work	do	2,432			
Old stone work	do	955			
Grade stones	42			
Bench Mark stones	2			
Total			
Sluice—						
No. I Sluice cutting and clearing	L. S.	20			
No. II Sluice—						
Earthwork	C. Yd.	400			
Brick in chunnam	C. Ft.	591			
Concrete	do	173			
Plastering	Sqr.	2,78			
Covering slabs	S. Ft.	117			
Front and orifice stones	L. S.	8			
Gibbet stones	do	15			
Total			
Waste weirs—						
Excavation	C. Yd.	3,706			
Brick in chunnam	C. Ft.	2,151			
Plastering	Sqr.	576			
Covering slabs	S. Ft.	291			
New stone work	C. Yd.	437			
Total			

C. T. UALLA
Executive E